

ABC DEMOLITION COMPANY LETTERHEAD

Construction Waste Management Plan Smith Building Demolition PSU Project # 01-23456.00

ABC Demolition Company, and its subcontractors, will complete the contracted scope of work in accordance with the governing local, state and federal laws and ordinances concerning the handling of clean fill and hazardous waste, and in accordance with the contract documents for the project.

In addition, ABC Demolition Company will strictly adhere to the following items:

- Asbestos containing Material Removal and Lead-based Paint Clean-up Performance Specification.
- Division 02, Section 02070- Selective Demolition.
- Division 02, Section 02110- Site Clearing.

While adhering to these laws and contract regulations, ABC Demolition Company will recycle and/or salvage a minimum of 75% of construction, demolition, and land clearing waste as follows:

- Salvage steel from existing buildings; estimated at 85 tons.
- Recycle clean-fill concrete and concrete masonry units from existing buildings and foundations to XYZ Recycling Company's local recycling center; estimated at 2,050 tons.
- Use on-site earth material to establish final grades in lieu of importing material from off site; estimated at 18,000 tons.
- Salvage existing asphalt to be used in mixing new asphalt; estimated at 1,500 tons.